

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-10027-00-00  
Spot: SWSESW Sec/Twnshp/Rge: 5-30S-8W  
330 feet from S Section Line, 1650 feet from W Section Line  
Lease Name: POMEROY J G Well #: 1  
County: KINGMAN Total Vertical Depth: 4258 feet

Operator License No.: 31337  
Op Name: WILDCAT OIL & GAS LLC  
Address: 10286 SW 170TH AVE  
NASHVILLE, KS 67112

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	300		300 SX
PROD	4.5	4300	1565	250 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/26/2011 8:00 AM

Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: RICHARD MCINTYRE Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: PER KCC REQUIREMENTS.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL  
Date/Time Plugging Completed: 07/26/2011 1:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SANDED BOTTOM OFF TWICE, TAGGED SAND @ 4030' SPOTTED 4 SX OF CEMENT. RIPPED CASING OFF @ 1565' PULLED TO 1300' SPOTTED 35 SXS CEMENT, PULLED CASING TO 850' SPOTTED 35 SX OF CEMENT PULLED CASING TO 330' CIRCULATED TO SURFACE WITH 125 SX OF CEMENT. USING 60/40 POS MIX W/3 % CC.

Perfs:

Top	Bot	Thru	Comments
4234	4238		MISSISSIPPI

RECEIVED  
AUG 10 2011  
KCC WICHITA

Remarks: QUALITY WELL SERVICE, CEMENTING EQUIPMENT--ALSO TICKET #5252

Plugged through: CSG

District: 02

Signed Bj Hope  
(TECHNICIAN)