

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-04886-00-00  
Spot: E2SWSW Sec/Twnshp/Rge: 27-11S-17W  
660 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: BAUMER B Well #: 38  
County: ELLIS Total Vertical Depth: 3637 feet

Operator License No.: 33190  
Op Name: NOBLE ENERGY, INC.  
Address: 1625 BROADWAY, STE 2200  
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.675	1350	0	416 SX
PROD	5.5	3633	0	125 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/05/2011 8:00 AM  
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP  
Proposal Rcvd. from: TOM KARST Company: NOBLE ENERGY, INC. Phone: (785) 639-6309

Proposed Plugging Method: Ordered 600 sxs 60/40 pozmix - 4% gel - 600# hulls - 13 sxs gel.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/05/2011 10:00 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated 1850' and 1320' - two holes each.  
Ran tubing 3616'. Basic Energy Services pumped 13 sxs gel - followed with 50 sxs 60/40 pozmix - 4% gel with 50# hulls.  
Pulled to 1857' - pumped 175 sxs cement with 125 # hulls - circulated cement. 8 5/8" backside dead.  
PTOH. Pumped 80 sxs cement.  
Max. P.S.I. 300#. S.I.P. 200#.  
Pumped 75 sxs down 8 5/8". Max. P.S.I. 300#. Blew hole in surface pipe below head.

Perfs:

Top	Bot	Thru	Comments
3633	3637	OH	Alt 1

Remarks: BASIC ENERGY SERVICES.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

AUG 08 2011

RECEIVED  
AUG 12 2011  
KCC WICHITA

Form CP-2/3

✓ 8/12/11