

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-03333-00-00  
Spot: SESESW Sec/Twnshp/Rge: 21-11S-17W  
330 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: BEMIS C Well #: 1  
County: ELLIS Total Vertical Depth: 3410 feet

Operator License No.: 33190  
Op Name: NOBLE ENERGY, INC.  
Address: 1625 BROADWAY, STE 2200  
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	1131	0	w/unknown sxs cmt
COND	15.5	33		
L1	5.5	2088		
PROD	7.625	3402	0	250 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/28/2011 9:00 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Revd. from: GERARD HOLINDE Company: NOBLE ENERGY, INC. Phone: (785) 639-6302

Proposed Plugging Method: Ordered 800 sxs 60/40 pozmix - 4% gel - 600# hulls - 13 sxs gel.  
Casing leak 2088'-2467' - squeezed with 250 sxs.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/28/2011 3:15 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Superior Perforators shot two hole shots at 1800' and 1120'.  
D.S.& W. Well Service RIH to 3400'.  
Basic Cementing rigged to tubing and pumped 13 sxs gel - followed with 75 sxs 60/40 pozmix - 4% gel with 50# hulls mixed in.  
Pulled tubing to 1518'. Basic Cementing rigged to tubing and pumped 375 sxs cement with 300# hulls mixed in - lost circulation.  
Pulled tubing to 1147'. Basic Cementing rigged to tubing and pumped 50 sxs cement with 50# hulls mixed in to circulate cement up 7" casing.  
Pulled tubing - rigged to 7" casing with a swedge and pumped 200 sxs cement to pressure 7" casing.  
Max. P.S.I. 350#. S.I.P. 300#.  
Pressured 10" casing to 100# P.S.I. - pressure made cement bleed off at head. No S.I.P.

Perfs:

Top	Bot	Thru	Comments
3407	3409		
3402	3407	OH	
3272	3284		
3220	3230		

Remarks: BASIC ENERGY SERVICES-TICKET #04678A.

Plugged through: TBG

District: 04

Signed [Signature]  
(TECHNICIAN)

RECEIVED

AUG 12 2011

Form CP-2/3

✓ 8/10/11

JUL 29 2011

KCC WICHITA