

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-03335-00-01
Spot: NESESW Sec/Twnshp/Rge: 21-11S-17W
902 feet from S Section Line, 3046 feet from E Section Line
Lease Name: BEMIS C Well #: 3
County: ELLIS Total Vertical Depth: 3467 feet

Operator License No.: 33190
Op Name: NOBLE ENERGY, INC.
Address: 1625 BROADWAY, STE 2200
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	1134	0	w/425 sxs cmt
COND	15	32	0	w/22 sxs cmt
L1	0	0	0	0
PROD	7	3405	0	125 SX CMT

Well Type: SWD UIC Docket No: D20029.0 Date/Time to Plug: 08/04/2011 9:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: GERARD HOLINDLE Company: NOBLE ENERGY, INC. Phone: (485) 639-6302

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 4% gel - 200 sxs common - 500# hulls.
Washed and milled on well for two days - got to 985' and was hitting metal in 3 1/2" casing.
OK'ed by Case Morris to plug - was loosing the hole.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/04/2011 11:00 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:


Superior Perforators perfed one hole shot at 951'.
D.S.& W. RIH with tubing to 980'.
Basic rigged to tubing and pumped 75 sxs 60/40 pozmix - 4% gel to circulate cement up 3 1/2" casing - no blow on 10 3/4" casing.
Pulled tubing - rigged to 3 1/2" casing with a swedge and pumped 10 sxs cement.
Max. P.S.I. 300#. S.I.P. 300#.
Rigged to 10 3/4" casing with a swedge and pumped 100 sxs cement.
Max. P.S.I. 200#.
Cement came up around 7" and 10 3/4" casing - no shut in pressure.
7" casing full of cement. 15" casing full of cement.

Remarks: BASIC ENERGY SERVICES-TICKET #04681-A.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN) RECEIVED

CM

AUG 12 2011 Form CP-2/3

KCC WICHITA

AUG 04 2011