

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-22077-00-00  
Spot: SW Sec/Twnshp/Rge: 17-11S-17W  
1320 feet from S Section Line, 3960 feet from E Section Line  
Lease Name: HADLEY D Well #: 21  
County: ELLIS Total Vertical Depth: 3479 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N WATER STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3479		
SURF	8.625	263	0	200 SX
PROD	5.5	3629	0	200 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/28/2011 9:00 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: MARK ROBBEN Company: MURFIN DRILLING CO., INC. Phone: (785) 735-4621

Proposed Plugging Method: Ordered 425 sxs 60/40 pozmix - 4% gel - 600# hulls.  
Lease worked up by Pat Staab.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/28/2011 12:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perf Tech perfed two shot holes at 1700' - 1100' - 600'.  
Murfin Drilling RIH to 3385'.  
Quality Cementing rigged to tubing and pumped 100 sxs cement with 200# hulls mixed in.  
Pulled tubing to 2300'. Quality Cementing rigged to tubing and pumped 100 sxs cement with 200# hulls.  
Pulled tubing to 1300' and pumped 130 sxs cement with 200# hulls mixed in to circulate cement to surface.  
Pulled Tubing. Topped with 15 sxs cement - hole standing full.  
Rigged to 8 5/8" casing and pumped instant pressure.  
Max. P.S.I. 500#. S.I.P. 500#.

Perfs:

Top	Bot	Thru	Comments
3481	3484		ARBUCKLE
3472	3476		ARBUCKLE
3458	3460		ARBUCKLE
3445	3448		ARBUCKLE
3439	3441		ARBUCKLE

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #5061.

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

(TECHNICIAN)

RECEIVED

AUG 12 2011

Form CP-2/3

KCC WICHITA

JUL 29 2011