

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-21620-00-00
Spot: NWSWSW Sec/Twnshp/Rge: 25-18S-28W
948 feet from S Section Line, 4744 feet from E Section Line
Lease Name: E SHAPLAND TRUST Well #: B 1
County: LANE Total Vertical Depth: 4600 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	211		140 SX
PC		2034		CEMENTED TO SURFACE
PKR	5.5	4344		
PROD	5.5	4594		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/28/2011 10:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: GARY ROWE Company: RITCHIE EXPLORATION Phone: (620) 214-0330

Proposed Plugging Method: RUN TBG TO BOTTOM & SPOT 35 SX CMT, 150# HULLS, GEL SPACER TO 2100'. THEN CMT TO SURFACE. 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/28/2011 1:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

****CASING LEAK @ 1747' CEMENTED WITH 300 SX CMT. STILL HAD A LEAK OFF****
RUN TBG TO 4144' & PUMP 25 SX GELLED WATER, 35 SX CMT & 150# HULLS.
PULL TBG TO 2100' & PUMP 200 SX CMT. CMT CIRCULATED. PULL TBG & TOP
OFF WITH 25 SX CMT. TIED ONTO BACKSIDE & PUMP 10 SX CMT. PRESSURED TO
500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4258	4263		
4218	4220		
4186	4195		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

RECEIVED
AUG 10 2011
KCC DODGE CITY

Signed

Michael Maier

(TECHNICIAN)

RECEIVED
AUG 15 2011
KCC WICHITA

Form SP-2
8/17/11