

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-06438-00-00
Spot: E2SESW Sec/Twnshp/Rge: 12-11S-18W
713 feet from S Section Line, 2889 feet from E Section Line
Lease Name: SITES SWD Well #: 1
County: ELLIS Total Vertical Depth: 3350 feet

Operator License No.: 33190
Op Name: NOBLE ENERGY, INC.
Address: 1625 BROADWAY, STE 2200
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1099	0	w/unknown sxs cmt
PROD	5.5	3348	0	w/unknown sxs cmt

Well Type: SWD UIC Docket No: D00836.0 Date/Time to Plug: 08/09/2011 9:00 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: TOM KARST Company: NOBLE ENERGY, INC. Phone: (785) 625-4052

Proposed Plugging Method: Ordered 550 sxs 60/40 pozmix - 4% gel - 600# hulls - 12 sxs gel.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/09/2011 12:40 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated two holes each at 1650' and 1085'.
Ran tubing to 3309'. Basic Energy pumped 12 sxs gel - followed with 50 sxs 60/40 pozmix - 4% gel with 100# hulls.
Pulled tubing to 1672' - pumped 350 sxs cement with 350# hulls mixed in - circulated cement out 5 1/2" casing.
PTOH. Pumped 50 sxs cement.
Max. P.S.I. 500#. S.I.P. 500#.
Hooked up to backside and pumped 100 sxs cement.
Max. P.S.I. 150#. Blew hole in surface pipe - stayed full of cement.

Perfs:

Top	Bot	Thru	Comments
2921	3155		

Remarks: BASIC ENERGY SERVICES. LEASE IS A TWIN TO SITES #9.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

RECEIVED

AUG 15 2011

KCC WICHITA

AUG 11 2011

cm

8/17/11

Form CP-2/3

ccfo MC

8/16