

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-151-22378-00-00  
Spot: NESWSENE Sec/Twnshp/Rge: 23-28S-14W  
2150 feet from N Section Line, 765 feet from E Section Line  
Lease Name: SMITH Well #: 1-23  
County: PRATT Total Vertical Depth: 4710 feet

Operator License No.: 31739  
Op Name: IUKA-CARMI DEVELOPMENT LLC  
Address: PO BOX 847  
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	270		WITH 275 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/27/2011 8:00 AM  
Plug Co. License No.: 34541 Plug Co. Name: NINNESCAH DRILLING LLC  
Proposal Rcvd. from: TERRY CUMMINGS Company: NINNESCAH DRILLING LLC Phone: (620) 933-2001

Proposed Plugging Method: 1ST PLUG AT 4477' WITH 50 SX CMT. 2ND PLUG AT 900' WITH 50 SX CMT. 3RD PLUG AT 300' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: NONE  
Date/Time Plugging Completed: 07/27/2011 12:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

1ST PLUG AT 4477' WITH 50 SX CMT. 2ND PLUG AT 900' WITH 50 SX CMT. 3RD PLUG AT 300' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: DP

District: 01

Signed Michael J Maier  
(TECHNICIAN)

RECEIVED

AUG - 4 2011

KCC DODGE CITY

RECEIVED

AUG 15 2011

KCC WICHITA

Form CP-2/3

8/17/11