

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-22410-00-00
Spot: SESESENW Sec/Twnshp/Rge: 11-19S-12W
2920 feet from S Section Line, 2920 feet from E Section Line
Lease Name: MILLER GEORGE Well #: 1
County: BARTON Total Vertical Depth: 3389 feet

Operator License No.: 31528
Op Name: MIKE KELSO OIL, INC.
Address: PO BOX 467
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	246	9	w/175 sxs cmt
PROD	4.5	3389	615	w/200 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/08/2011 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE KELSO OIL, INC. Phone: (620) 562-8088

Proposed Ordered 500 sxs 60/40 pozmix - 4% gel.
Plugging Junk in the well at 2650' - 2 3/8" tubing - 4 1/2" casing parted - pulled 615'.
Method: Ran 7" casing to 615'. Welded to 8.625" surface pipe.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/08/2011 11:30 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 615' - pumped 100 sxs cement - cement circulated.
POOH. Hooked up to 7" casing and pumped 330 sxs cement.
Cement circulated - closed valve on the backside and pumped 25 sxs cement.
Max. P.S.I. 500#.

Perfs:

Remarks: COPELAND ACID AND CEMENTING COMPANY-TICKET #36924.

Plugged through: TBG

District: 04

Signed

R. A. Dinkel

(TECHNICIAN)

RECEIVED

AUG 15 2011

CM

KCC WICHITA

Form CP-2/3

8/17/11

AUG 11 2011