

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-02355-00-00
Spot: SENESE Sec/Twnshp/Rge: 31-10S-17W
1650 feet from S Section Line, 330 feet from E Section Line
Lease Name: RIDLER G Well #: 1
County: ROOKS Total Vertical Depth: 3515 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: 370 W WICHITA AVE PO BOX 352
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1243	0	600 sx
PROD	5.5	3514	0	250 sx

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/09/2011 12:00 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DUANE EICHMAN Company: FARMER, JOHN O., INC. Phone: (785) 483-8355

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 500# hulls - 16 sxs gel.
CIBP at 3380' with one sack of cement on top.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/09/2011 3:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated two holes at 1200'.
Ran tubing to 3340'. Allied pumped 16 sxs gel - followed with 50 sxs 60/40 pozmix - 4% gel with 200# hulls.
Pulled tubing to 650' - pumped 185 sxs cement - cement circulated.
PTOH. Pumped 20 sxs down 5 1/2".
Max. P.S.I. 700#. S.I.P. 700#.
Hooked up to 8 5/8" - pumped 35 sxs cement.
Max. P.S.I 700#. S.I.P. 700#.

Perfs:

Top	Bot	Thru	Comments
3514	3516		ARBUCKLE
3265	3361		LKC

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

cm

AUG 11 2011

RECEIVED Form CP-2/3

AUG 15 2011 8/15/11

KCC WICHITA