

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-083-10230-00-00
Spot: NWNE Sec/Twnshp/Rge: 8-22S-22W
4620 feet from S Section Line, 1980 feet from E Section Line
Lease Name: MILLER EST Well #: 3
County: HODGEMAN Total Vertical Depth: 4508 feet

Operator License No.: 6931
Op Name: BOWMAN OIL COMPANY, A GENERAL
Address: 805 CODELL RD
CODELL, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3914		WITH 2 SX CMT
SURF	8.625	255		WITH 200 SX CMT
PROD	5.5	4492	0	WITH 100 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/29/2011 8:30 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: DONALD A. BOWMAN Company: BOWMAN OIL Phone: (785) 259-4154

Proposed Plugging Method: SET CIBP @ 4400' WITH 2 SX CMT. PRESSURE TEST CASING TO FIND LEAKS. PLUG AT 1500' WITH 50 SX CMT. PERFORATE AT 600' & CIRCULATE CMT TO SURFACE. CHECK BACKSIDE WITH 50 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/29/2011 4:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

1ST PLUG SET CIBP @ 3914' & 2 SX CMT. 2ND PLUG RAN TBG & PACKER AND LOCATED HOLES IN CASING BETWEEN 1360' & 1420'. PULLED PACKER. TIHWT TO 1500'. PUMPED 75 SX CMT. 3RD PLUG TOH. WAIT ON CMT 1.5 HOURS. TAGGED TOC @ 1300'. 4TH PLUG PERFORATED CASING AT 600'. RAN TBG TO 600'. CIRCULATED 5 1/2" & 8 5/8" CASING WITH 95 SX SMD CMT. 5TH PLUG TOH FILLED CASING WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4492	4510		Mississippian

Remarks: USED 60/40 POZMIX & SMD BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed Eric MacLaren
(TECHNICIAN)

RECEIVED
AUG - 9 2011
KCC DODGE CITY

RECEIVED
AUG 15 2011
KCC WICHITA

Form CR-23
8/17/11