

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-083-21719-00-00
Spot: SWSWNWSE Sec/Twnshp/Rge: 8-23S-22W
1350 feet from S Section Line, 2379 feet from E Section Line
Lease Name: DENNIS-DONALD Well #: 1-8
County: HODGEMAN Total Vertical Depth: 4564 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	222		WITH 150 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/05/2011 5:30 PM
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.
Proposal Rcvd. from: KEN MCGUIRE Company: DUKE DRILLING CO., INC. Phone: (316) 267-1331

Proposed Plugging Method: 1ST PLUG AT 1460' WITH 50 SX CMT. 2ND PLUG AT 620' WITH 60 SX CMT. 3RD PLUG AT 240' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: NONE
Date/Time Plugging Completed: 08/05/2011 7:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

1ST PLUG AT 1460' WITH 50 SX CMT. 2ND PLUG AT 620' WITH 60 SX CMT. 3RD PLUG AT 240' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

Signed Michael J. Maier
(TECHNICIAN) RECEIVED

RECEIVED
AUG - 9 2011
KCC DODGE CITY

AUG 15 2011 Form CP-2/3
KCC WICHITA 8/17/11