

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-20511-00-00
Spot: N2NWNW Sec/Twnshp/Rge: 27-30S-6W
4770 feet from S Section Line, 4620 feet from E Section Line
Lease Name: CRANE B Well #: 1
County: KINGMAN Total Vertical Depth: 4490 feet

Operator License No.: 31337
Op Name: WILDCAT OIL & GAS LLC
Address: 10286 SW 170TH AVE
NASHVILLE, KS 67112

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	220		165 SXS CMT
PROD	4.5	4486		250 SXS CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/29/2011 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: SAND 50' ABOVE TOP PERFS & 4 SKS CMT. REC PIPE, 35 SX 1100', 35 SX 750' CIRC TO 270

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 07/29/2011 12:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A CIBP WAS SET AT 3500' TO COVER PERFS. COVERED CIBP WITH 2 SKS CMT. REC 1945' OF 4 1/2" CASING. PULLED CASING TO 1100', SPOTTED 35 SXS CEMENT. PULL CASING TO 750', SPOTTED 35 SKS CMT. PULLED CASING TO 270' & CIRC HOLE FULL OF CMT. PULLED CASING & TOPPED OFF.

Perfs:

Top	Bot	Thru	Comments
3667	3669	CSG	
3638	3640	CSG	
3560	3562	CSG	
3551	3553	CSG	

Remarks: QUALITY WELL SERVICE 60/40 4% GEL

Plugged through: CSG

District: 02

Signed _____



(TECHNICIAN)

RECEIVED Form CP-2/3
AUG 17 2011 8/23/11

KCC WICHITA