

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-21118-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 12-17S-9W
2234 feet from S Section Line, 2430 feet from E Section Line
Lease Name: OSBOURN TWIN Well #: 1
County: ELLSWORTH Total Vertical Depth: 2550 feet

Operator License No.: 4976
Op Name: SOUTHWEST OPERATING COMPANY
Address: 10551 BARKLEY STE # 108 PO BOX 25
OVERLAND PARK, KS 66212

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	346		180 SX
T1	2.5	2429		
PROD	4.5	2534	1631	115 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/18/2011 8:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMES HARRIS Company: MIKES TESTING & SALVAGE Phone: (620) 562-0895

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 07/18/2011 12:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, PULL RODS AND TUBING OUT. SAND PERFS TO 2120' AND CAP WITH 4 SX'S CEMENT. CUT CASING AT 1631' AND PULL TO 1150' AND PUMP 35 SX'S COMMON CEMENT WITH 100#'S COTTON HULLS. PULL CASING UP TO 800'-LET CEMENT SET FOR 1 HR. RUN SANDLINE DOWN-TAGGED CEMENT AT 1321'. RUN 4.5" CASING BACK IN HOLE TO 1150' AND PUMPED 50 SX'S COMMON CEMENT WITH GOOD CIRCULATION. PULL CASING TO 800' AND PUMP 35 SX'S CEMENT WITH GOOD CIRCULATION. PULL CASING TO 400' AND CIRCULATE CEMENT TO SURFACE. PULL CASING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
2428	2435	CSG	
2174	2178	CSG	

Well plugged because operator failed to comply with K.A.R. R2-3-111, also failed to close pits.

Remarks: 60-40 POZ, 4% GEL--EXCEPT WHERE COMMON USED. C-36908.

Plugged through: CSG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

RECEIVED
AUG 17 2011
KCC WICHITA

Form CP-2/3
8/23/11