

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-19440-00-00
Spot: SWNWNWNW Sec/Twnshp/Rge: 14-30S-4E
600 feet from N Section Line, 200 feet from W Section Line
Lease Name: MAGNUSON Well #: 1
County: COWLEY Total Vertical Depth: 1730 feet

Operator License No.: 6044
Op Name: STELBAR OIL CORPORATION, INC.
Address: 1625 N WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	105		5 YDS.

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/20/2011 8:00 AM

Plug Co. License No.: 6044 Plug Co. Name: STELBAR OIL CORPORATION, INC.

Proposal Rcvd. from: ROB WILLIAMS Company: STELBAR OIL CORPORATION, IN Phone: (316) 264-8378

Proposed Plugging Method: PER KCC INSTRUCTIONS. NOTE: WELL WAS DRILLED AND ABANDONED BY SINCLAIR IN 1928. HAVE NO RECORDS ON HOW WELL WAS PLUGGED.

Plugging Proposal Received By: DUANE KRUEGER
Date/Time Plugging Completed: 06/23/2011 12:00 AM

Witness Type: NONE
KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

RIH W/WORKSTRING @ 1730', CIRCULATED HOLE CLEAN & SPOTTED 50 SXS 60/40 POZMIX 4% GEL & DISPLACED IN OPEN HOLE. PULLED WORKSTRING @ 262 CIRCULATED 300 SXS 60/40 POZMIX 4% GEL TO SURFACE. 6-23-2011, TAGGED CEMENT @ 110', RIH W/WORKSTRING @ 105', CIRCULATED 75 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 6-23-2011 @ 12:00 AM.

Remarks:

Plugged through: TBG

District: 02

Signed _____

(TECHNICIAN)

RECEIVED ✓

Form CP-2/3

AUG 17 2011

8/23/11

KCC WICHITA