

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-01957-00-00  
Spot: SENWNW Sec/Twnshp/Rge: 36-18S-8W  
4290 feet from S Section Line, 4077 feet from E Section Line  
Lease Name: R J WARNER A Well #: 3  
County: RICE Total Vertical Depth: 3227 feet

Operator License No.: 9292  
Op Name: SCHECK, TIMOTHY DBA SCHECK OIL  
Address: 211 S FRONT ST  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	199		50 SX
T1	3.5	0	1210	
PROD	6	3194		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/18/2011 3:30 PM  
Plug Co. License No.: 33369 Plug Co. Name: XTREME WELL SERVICE, INC.  
Proposal Rcvd. from: LEON HUXMAN Company: SCHECK OIL OPERATION Phone: (785) 483-0567

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL  
Date/Time Plugging Completed: 07/18/2011 6:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:   
MIRU, FOUND 3" TUBING TO BE STUCK. WAS FINALLY ABLE TO FREE TUBING AT 1210'. PERFORATED AT 1075', 725' AND 250'. RUN TUBING TO 1075' AND PUMP 35 SX'S CEMENT. LET SET FOR AWHILE AND TAGGED AT 1055'. PULLED TUBING TO 725' AND PUMPED 35 SX'S CEMENT, PULLED TUBING TO 250' AND CIRCULATED CEMENT TO SURFACE. PULLED TUBING OUT AND PUMPED CEMENT -- PRESSURED UP TO 500#S-SHUT IN. CAME BACK ON 7-19-11, CEMENT DOWN APPROX. 6-7'. USED 250 SX'S CEMENT.

*Well plugged in response to N.O.V. sent, for 7/18 violation. Compliance deadline before submitted to legal.*

Perfs:

Remarks: 60-40 POZ, 4% GEL. LOG TECH OF KS. #6630. ALLIED TICKET #039664.

Plugged through: TBG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

RECEIVED  
AUG 17 2011  
KCC WICHITA

Form CP-2/3  
8/28/11

JK