

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-01958-00-00  
Spot: NESENW Sec/Twnshp/Rge: 36-18S-8W  
3608 feet from S Section Line, 2978 feet from E Section Line  
Lease Name: R J WARNER A Well #: 4  
County: RICE Total Vertical Depth: 3224 feet

Operator License No.: 9292  
Op Name: SCHECK, TIMOTHY DBA SCHECK OIL  
Address: 211 S FRONT ST  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	204		50 SX
PROD 6		3204		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/19/2011 4:30 PM  
Plug Co. License No.: 33369 Plug Co. Name: XTREME WELL SERVICE, INC.  
Proposal Rcvd. from: LEON HUXMAN Company: XTREME WELL SERVICE INC. Phone: (785) 483-0567

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL  
Date/Time Plugging Completed: 07/19/2011 8:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, ENCOUNTERED OBSTRUCTION AT 630'--GOT ON THRU AND RAN DOWN TO BOTTOM. PERFORATE AT 1075', 725', AND 250'. RUN TUBING TO 3153' AND PUMP 50 SX'S CEMENT, PULLED TUBING TO 1075' AND PUMPED 50 SX'S CEMENT, PULLED TUBING TO 725' AND PUMPED 50 SX'S CEMENT WITH GOOD CIRCULATION, PULLED TUBING--CONNECTED ONTO CASING AND CIRCULATED CEMENT TO SURFACE--PRESSURED UP TO 400#S AND SHUT IN. USED 275 SX'S CEMENT.

Perfs:

Top	Bot	Thru	Comments
3204	3224	OH	

*Well plugged in response to NOV letter sent for T/A violation. Compliance deadline be five submitted to legal.*

Remarks: 60-40 POZ, 4% GEL. LOG TECH OF KS TICKET #6649. ALLIED TICKET #040233.

Plugged through: TBG

RECEIVED

AUG 17 2011

KCC WICHITA

District: 02

Signed

Virgil Clothier  
(TECHNICIAN)

Form CP-2/3

8/23/11

JK