

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-19121-00-00

Spot: NWNWSW

Sec/Twnshp/Rge: 8-35S-4E

2339 feet from S Section Line, 5063 feet from E Section Line

Lease Name: KLINK B

Well #: 5

County: COWLEY

Total Vertical Depth: 3400 feet

Operator License No.: 33293

Op Name: PRYOR, VICTOR W., JR.

Address: PO BOX 898

HOLDENVILLE, OK 74848

String	Size	Depth (ft)	Pulled (ft)	Comments
--------	------	------------	-------------	----------

SURF	8.625	197		150 SX
------	-------	-----	--	--------

PROD	4.5	3320	2775	
------	-----	------	------	--

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 08/04/2011 8:00 AM

Plug Co. License No.: 34271

Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.

Proposal Rcvd. from: KENNETH KIVETT

Company: KIVETT PLUGGING & PIPE PLUGG Phone: (405) 379-2252

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER

Witness Type: PARTIAL

Date/Time Plugging Completed: 08/04/2011 5:00 PM

KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SET CIBP @ 3220', DUMP BAILED 2 SXS CEMENT ON TOP. 8-4-2011, CUT 4-1/2" CSG @ 2775', LAYED DOWN 86 JTS 4-1/2" CASING. RIH W/TBG @ 250', MIXED & PUMPED 150 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 PM 8-4-2011. CEMENT TICKET #10685.

Perfs:

Top	Bot	Thru	Comments
3320	3400	OH	

Remarks: TA'S DENIED

Plugged through: TBG

RECEIVED

AUG 17 2011

KCC WICHITA

District: 02

Signed

(TECHNICIAN)

Form CP-2/3

8/23/11

JK