

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-22176-00-00
Spot: S2W2NWNW Sec/Twnshp/Rge: 6-30S-8W
750 feet from N Section Line, 560 feet from W Section Line
Lease Name: LILJA Well #: 1
County: KINGMAN Total Vertical Depth: 4212 feet

Operator License No.: 4706
Op Name: MESSENGER PETROLEUM, INC.
Address: 525 S MAIN ST
KINGMAN, KS 67068

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	3865		
CIBP	4.5	4100		
SURF	8.625	225		225 SX
T1	2.375	4113		
PKR		4113		
PROD	4.5	4208	2830	150 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/18/2011 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 532-5400

Proposed Plugging Method: SAND TO 3780 & 4 SKS CMT. 35 SXS 1200, 35 SXS 850, CIRC 275-0

Plugging Proposal Received By: JEFF KLOCK Witness Type: NONE
Date/Time Plugging Completed: 07/18/2011 12:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:
THE PERF WHERE COVERED WITH SAND TO 3780 & 4 SKS CMT. THE CASING WAS RECOVERED FROM 2830' & PULLED TO 1200', WHERE 35 SKS CMT @ 100# OF HULLS WAS SPOTTED. THE CASING WAS PULLED TO 850' WHERE 35 SXS OF CMT & 100#S OF HULLS WAS SPOTTED. THE CASING WAS PULLED TO 275' WHERE CMT WAS CIRC'D TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4127	4137	CSG	MISS
3874	3876	CSG	HERTHA
3840	3842	CSG	SWOPE

Remarks: QUAILTY WELL SERVICE #5298. 60/40 4% GEL & 3% CACL
Plugged through: CSG

District: 02

Signed _____
(TECHNICIAN)

RECEIVED
AUG 17 2011 8/23/11
Form CP-2/5
KCC WICHITA