

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-30058-00-01
Spot: NENW Sec/Twnshp/Rge: 16-29S-8W
660 feet from N Section Line, 1980 feet from W Section Line
Lease Name: ROBINSON Well #: 1
County: KINGMAN Total Vertical Depth: 4382 feet

Operator License No.: 4706
Op Name: MESSENGER PETROLEUM, INC.
Address: 525 S MAIN ST
KINGMAN, KS 67068

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	3886		
CIBP	4.5	4135		
SURF	8.625	253		175 SX
T1	2.875	4140		
PROD	4.5	4360	1596	150 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/21/2011 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 532-5400

Proposed Plugging Method: SAND TO 3787' & 4 SKS. 35 SX 100# HULL 1300', 35 SX 100# HULL 850', CIRC 140 SK 300'-0'.

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL
Date/Time Plugging Completed: 07/21/2011 10:00 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERF WERE COVERED WITH SAND TO 3787' & CAPPED WITH 4 SKS CMT. THE CASING WAS RECOVERED FROM 1596' & PULLED TO 1300' WHERE 35 SXS 3% CACL & 100# HULLS WERE SPOTTED. THE CASING WAS PULLED TO 850' WHERE 35 SXS 3% CACL & 100# HULLS WAS SPOTTED. THE CASING WAS PULLED TO 300' WHERE CMT WAS CIRCD WITH 140 SKS CMT.

Perfs:

Top	Bot	Thru	Comments
4162	4166	CSG	MISS
3896	3900	CSG	HERTHA
3858	3862	CSG	SWOPE

Remarks: QUALITY WELL SERVICE 60/40 4% GEL 3% CACL

Plugged through: CSG

District: 02

Signed _____

(TECHNICIAN)

RECEIVED 8/22/11
AUG 17 2011
KCC WICHITA