

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-19508-00-00  
Spot: NW NESW Sec/Twnshp/Rge: 3-28S-6E  
2359 feet from S Section Line, 3636 feet from E Section Line  
Lease Name: BLAKEMAN NORTH Well #: 2  
County: BUTLER Total Vertical Depth: 3052 feet

Operator License No.: 30582  
Op Name: KISER, MICHAEL DBA MWK PETROLE  
Address: 508 STONE LK CT  
AUGUSTA, KS 67010

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	6.625	2780		
COND	8.625	2260		
PROD	5.5	3047		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/01/2011 8:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: AS PER KCC RULES & REGS, SET BOTTOM PLUG, FILL OPEN HOLE PLUS 50' THEN 5 SXS CEMENT. PULL CASING. PUMP CEMENT FROM 250' TO SURFACE.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 07/06/2011 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED OPEN HOLE BACK @ 2985', DUMP BAILED 5 SXS CEMENT ON TOP. PERFORATED SQUEEZE HOLES @ 250'-251', QUALITY WELL SERVICE MIXED & PUMPED 85 SXS 60/40 POZMIX 4% GEL TO SURFACE, CEMENT CIRCULATED. PLUG DOWN 7-6-2011, 5:00 P.M. NO CEMENT TICKET #.

Perfs:

Top	Bot	Thru	Comments
3047	3052	OH	OPEN HOLE

RECEIVED

AUG 17 2011

KCC WICHITA

Remarks:  
Plugged through: TBG

District: 02

Signed Duane Krueger  
(TECHNICIAN)

8/28/11

JK