

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-20728-00-00
Spot: NESWSESW Sec/Twnshp/Rge: 3-28S-6E
496 feet from S Section Line, 3540 feet from E Section Line
Lease Name: BLAKEMAN SOUTH Well #: 7
County: BUTLER Total Vertical Depth: 3039 feet

Operator License No.: 30582
Op Name: KISER, MICHAEL DBA MWK PETROLE
Address: 508 STONE LK CT
AUGUSTA, KS 67010

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	186		125 SX
PROD	5.5	3034		75 SXS CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/07/2011 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: AS PER KCC RULES & REGS, SET BOTTOM PLUG, FILL OPEN HOLE PLUS 50' THEN 5 SXS CEMENT. PULL CASING. PUMP CEMENT FROM 250' TO SURFACE.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: NONE
Date/Time Plugging Completed: 07/08/2011 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED OPEN HOLE BACK @ 2970', DUMP BAILED 5 SXS CEMENT ON TOP. PERFORATED SQUEZE HOLES @ 250'-251', QUALITYWELL SERVICE MIXED & PUMPED 85 SXS 60/40 POZMIX 4% GEL TO SURFACE, CEMENT CIRCULATED. PLUG DOWN 7-8-2011, 5:00 P.M. NO CEMENT TICKET #.

Perfs:

Top	Bot	Thru	Comments
3034	3039	OH	OPEN HOLE

Remarks:

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)

RECEIVED

AUG 17 2011

Form CP-2/3

8/23/11

KCC WICHITA