

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-21929-00-00  
Spot: NESESW Sec/Twnshp/Rge: 3-28S-6E  
1289 feet from S Section Line, 2980 feet from E Section Line  
Lease Name: BLAKEMAN SOUTH Well #: 9  
County: BUTLER Total Vertical Depth: 3055 feet

Operator License No.: 30582  
Op Name: KISER, MICHAEL DBA MWK PETROLE  
Address: 508 STONE LK CT  
AUGUSTA, KS 67010

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	208		75 SXS CMT
PROD	5.5	3050		50 SXS CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/06/2011 8:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: AS PER KCC RULES & REGS, SET BOTTOM PLUG, FILL OPEN HOLE PLUS 50' THEN 5 SXS CEMENT. PULL CASING. PUMP CEMENT FROM 250' TO SURFACE.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: NONE  
Date/Time Plugging Completed: 07/07/2011 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:  
SANDED OPEN HOLE BACK @ 2990', DUMP BAILED 5 SXS CEMENT ON TOP.  
PERFORATED SQUEEZE HOLES @ 250'-251', QUALITY WELL SERVICE MIXED &  
PUMPED 85 SXS 60/40 POZMIX 4% GEL TO SURFACE, CEMENT CIRCULATED.  
PLUG DOWN 7-7-2011, 5:00 P.M. NO CEMENT TICKET #.

Perfs:

Top	Bot	Thru	Comments
3050	3055	OH	OPEN HOLE

Remarks:  
Plugged through: TBG

RECEIVED  
AUG 17 2011  
KCC WICHITA

District: 02 Signed: Duane Krueger  
(TECHNICIAN)

Form CP-2/3  
8/23/11

JK