

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-30083-00-01
Spot: NENESW Sec/Twnshp/Rge: 34-27S-5W
2310 feet from S Section Line, 2310 feet from W Section Line
Lease Name: YOUNG T Well #: 1-34 RE
County: KINGMAN Total Vertical Depth: 4130 feet

Operator License No.: 5214
Op Name: LARIO OIL & GAS COMPANY
Address: 301 S MARKET ST
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	197		165 SX
T1	2.375	3747		
PROD	5.5	4101		145 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/13/2011 1:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 297-3222

Proposed Plugging Method: SAND TO 3700 & 5 SKS. 35 SXS @ 900'. CIRC 350'-0'.

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 07/14/2011 1:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

PUMPED 35 SXS PLUG ON BOTTOM. TAGGED CMT @ 3500'. STILL HAD GAS. SET CIBP @ 2940' & 5 SKS CMT. RECOVERED 2615' OF 5 1/2 SPOTTED 35 SXS @ 900' CIRC CMT FROM 350'-0'. CMT FELL 100', TOPPED OFF.

Perfs:

Top	Bot	Thru	Comments
3758	3780	CSG	

Remarks: QWS CEMENTING 60/40 4%

Plugged through: CSG

RECEIVED
AUG 17 2011
KCC WICHITA

District: 02

Signed _____

(TECHNICIAN)