

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-22046-00-03
Spot: SWSENE SW Sec/Twnshp/Rge: 3-35S-1E
1505 feet from S Section Line, 2982 feet from E Section Line
Lease Name: BATES Well #: 8
County: SUMNER Total Vertical Depth: 3900 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 1321 W 93 N PO BOX 560
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	260		175 sxs
PROD	5.5	3713	1406	300 sxs

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/29/2011 8:00 AM
Plug Co. License No.: 99981 Plug Co. Name: COPELAND ACID & CEMENT, INC.
Proposal Rcvd. from: ALBERT COOPER Company: COOPER SERVICE CO. Phone: (316) 204-0072

Proposed Plugging Method: AS PER KCC RULES & REGS, SET CIBP @ 3615 W/5 SXS, CIRC 310'-0'

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 06/29/2011 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SET CIBP @ 3350', DUMP BAILED 5 SXS CEMENT ON TOP. CUT CASING @ 1540', LAYED DOWN 34 JOINTS 5-1/2" CASING (1540'). RIH W/TBG @ 325', COPELAND ACID SERVICE MIXED & PUMPED 240 SXS 60/40 POZ MIX 2% GEL, 2% CC. TO SURFACE. CEMENT CIRCULATED. COPELAND ACID SERVICE CEMENT TICKET #37711. 6-30-2011, TOPPED WELL BACK TO SURFACE W/15 SXS.

Perfs:

Top	Bot	Thru	Comments
3664	3672	CSG	Simpson
3600	3604	CSG	Simpson
3587	3589	CSG	Simpson

Remarks:

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)

RECEIVED Form CP-2/3

AUG 17 2011 8/23/11

KCC WICHITA