

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-22085-00-00
Spot: NESWSW Sec/Twnshp/Rge: 3-35S-1E
1006 feet from S Section Line; 4297 feet from E Section Line
Lease Name: BATES Well #: 10
County: SUMNER Total Vertical Depth: 3780 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 1321 W 93 N PO BOX 560
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	268		200 sxs
PROD	5.5	3780	1530	100 sxs

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 06/30/2011 8:00 AM
Plug Co. License No.: 99981 Plug Co. Name: COPELAND ACID & CEMENT, INC.
Proposal Rcvd. from: ALBERT COOPER Company: COOPER SERVICE CO Phone: (316) 204-0072

Proposed Plugging Method: AS PER KCC RULES & REGS, SET CIBP @ 3552 W/5 SXS, CIRC 318'-0'

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 06/30/2011 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SET CIBP @ 3550', DUMP BAILED 5 SXS CEMENT ON TOP. CUT CASING @ 1530', LAYED DOWN 34 JOINTS 5-1/2" CASING (1530'). RIH W/TBG @ 325', COPELAND ACID SERVICE MIXED & PUMPED 245 SXS 60/40 POZMIX 2% GEL, 2% CC. TO SURFACE. CEMENT CIRCULATED. COPELAND ACID SERVICE CEMENT TICKET #37713. P & A COMPLETE.

Perfs:

Top	Bot	Thru	Comments
3602	3606	CSG	Simpson
3596	3600	CSG	Simpson

Remarks:
Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)

RECEIVED Form CP-2/3
AUG 17 2011 8/23/11
KCC WICHITA

JK