

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-21359-00-00  
Spot: SWNWSE Sec/Twnshp/Rge: 10-19S-6W  
1650 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: ROLFS Well #: 1  
County: RICE Total Vertical Depth: 3400 feet

Operator License No.: 30931  
Op Name: DAYSTAR PETROLEUM, INC.  
Address: 1321 W 93 N PO BOX 560  
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	3220		
SURF	8.625	217		130 sx
PROD	5.5	3356	1835	125 sx

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/13/2011 9:30 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: JAMIE HARRIS Company: MIKES TESTING & SALVAGE Phone: (620) 562-0895

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: DUANE KRUEGER Witness Type: NONE  
Date/Time Plugging Completed: 07/13/2011 2:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, SANDED BOTTOM TO 3050' & CAPPED WITH 5 SX'S. CUT CASING AT 1835', PULLED TO 900' & PUMP 35 SX'S COMMON CEMENT, 2 SX'S CC & 150#'S COTTON HULLS. LET SET 1 HOUR - RETAGGED @ 882'. PUMP 35 SX'S THRU CASING @ 550', PULL TO 270' & CIRCULATE CEMENT TO 0'. PULL CASING OUT & TOP OFF. USED 290 SX'S.

Perfs:

Top	Bot	Thru	Comments
3266	3269	CSG	
3126	3131	CSG	

\* 10 YR TA

Remarks: 60-40 POZ, 4% GEL. COPELAND TICKET C-36905.

Plugged through: CSG

District: 02

Signed

*Virgil Clothier*

(TECHNICIAN)

RECEIVED

AUG 17 2011

Form CP-2/3

8/23/11

KCC WICHITA