

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-053-20944-00-00  
Spot: NWNWNE Sec/Twnshp/Rge: 6-16S-10W  
5263 feet from S Section Line, 2365 feet from E Section Line  
Lease Name: ZVOLANEK Well #: 2  
County: ELLSWORTH Total Vertical Depth: 3309 feet

Operator License No.: 3682  
Op Name: CONNELL, MARK ALLEN  
Address: 606 W ALBRO ST  
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	3050		12' SAND IN OPEN HOLE
SURF	8.625	337		210 SX
PROD	5.5	3302		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/09/2011 1:00 PM  
Plug Co. License No.: 30081 Plug Co. Name: ANSHUTZ, EVELYN DBA ANSHUTZ OIL  
Proposal Rcvd. from: MARK CONNELL Company: \_\_\_\_\_ Phone: (620) 786-1228

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL  
Date/Time Plugging Completed: 08/09/2011 4:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, WELL WAS SQUEEZED BACK IN 1985 WITH 700 SX'S CEMENT, SAW MOHAWK DRILLING. INC. INVOICES #1361 & 1374. CEMENT ON BACKSIDE OF CASING THRU SALT SECTION. SANDED OPEN HOLE AND SET CIBP AT 3050'. PERFORATE AT 380'. RUN TUBING TO 3040' AND PUMP 35 SXS CEMENT. PULL TUBING ON UP TO 680'. LET SET AND TAG CEMENT AT 2680'. PUMP GEL AT 680', THEN PULLED TUBING ON UP TO 380' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND CONNECT SWAGE ON TO CASING, PUMP CEMENT-PRESSURED UP TO 200#S, STAYED PRESSURED. DISCONNECTED FROM CASING STAYED FULL OF CEMENT. DRIED CEMENT WAS PRESENT IN SURFACE CASING.

Perfs:

Top	Bot	Thru	Comments
3302	3309	OH	
2999	3009	CSG	2HPF
980	981		4HPF, SQUEEZE JO

*Well plugged due to Compliance; Penalty order issued because operator failed to follow requirements under K.A.R. 82-3-111*

Remarks: 60-40 POZ 4% GEL. LOG TECH OF KS. #6642. COPELAND TICKET # C-36998.

Plugged through: TBG

RECEIVED  
AUG 17 2011  
KCC WICHITA

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

Form CP-2/3  
8/23/11

JK