

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-191-20187-00-01  
Spot: SESESW Sec/Twnshp/Rge: 18-35S-4W  
330 feet from S Section Line, 2310 feet from W Section Line  
Lease Name: HYENA OWWO Well #: 1  
County: SUMNER Total Vertical Depth: 5462 feet

Operator License No.: 3532  
Op Name: CMX, INC.  
Address: 1700 N WATERFRONT PKWY BLDG 300  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	259		200 SX
T1	2.875	4774		
PROD	5.5	5462		200 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/11/2011 9:30 AM  
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION  
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5664

Proposed Plugging Method: 35 SX, 1050, 35, 700, CIRC 310

Plugging Proposal Received By: DAN FOX Witness Type: PARTIAL  
Date/Time Plugging Completed: 07/11/2011 11:00 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

CIBP AT 4840 & 2 SKS, RECOVERED 2600' 5 1/2 CASING, PULLED FROM WELL RAN TUBING TO 1050' SPOTTED 35 SX, PULLED TUBING TO 700' SPOTTED 35 SX PULLED TUBING TO 310' & CIRC CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5058	5060		MISSISSIPPI
5034	5042		MISSISSIPPI
4961	4974		MISSISSIPPI
4918	4942		
4912			
4890	4896		MISSISSIPPI

Remarks: ALLIED CEMENT 60/40 4% GEL. PLUGGED TA STATUS

Plugged through: TBG

District: 02

Signed \_\_\_\_\_

(TECHNICIAN)

RECEIVED  
AUG 17 2011

Form CP-2/3  
8/23/11

KCC WICHITA