

15-007-02387-00-00

Form CP-3  
Rev. 6-26-62

**KANSAS**  
**STATE CORPORATION COMMISSION**

**CONSERVATION DIVISION AGENT'S REPORT**

**RECEIVED**  
STATE CORPORATION COMMISSION

AUG 18 1964  
8-18-64  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Bowers Drilling Co., Inc.

Complete Address: 1434 Wichita Plaza, Wichita, Kansas

Lease Name Magnison Well No. # 1

Location C NW SE Sec. 34 Twp. 32 Rge. 13 (E) (W) W

County Barber Total Depth 4537

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Bowers Drilling Co., Inc.

Address: 1434 Wichita Plaza, Wichita, Kansas License No.     

Operation Completed: Hour 2:30 AM Day 17th Month August Year 1964

The Above well was plugged as follows:

314' of 8 5/8" surface pipe, cement circulated with 225 sacks. Fluid  
level in the hole was at 240'. 1st cementing plug, bridged solid with  
hulls, on fluid at 240', and cemented with 25 sacks, through the drill  
pipe. Hole was filled with drilling mud to 40', 2nd cementing plug,  
bridged solid with hulls, on fluid at 40', and cemented with 10 sacks  
to the base of the cellar. Rat hole bridged and cemented with 5 sacks.  
This cementing was done by Globe Cementing Company.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**  
DATE 8/18/64  
INV. NO. 9663-W

Signed: Archie Elving  
Well Plugging Supervisor