

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 8 1967
5-8-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Cities Service Oil Company,

Complete Address: P.O. Box #6, Liberal, Kansas.

Lease Name Pfeffinger Well No. A-1

Location CSW-SW Sec. 29 Twp. 20 Rge. (E) (W) 34

County Scott Total Depth 4663

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Sargent's Casing Pulling,

Address: Box #506, Liberal, Kansas. License No. 511

Operation Completed: Hour 12:00M Day 4 Month 5 Year 1967

The Above well was plugged as follows:

452'--8 5/8" Surface pipe, cement circulated with 275 Sx.
4660'--4 1/2" Production casing cemented with 175 Sx. Top of cement @ 3800'
(Temp Survey). Well plugged back to 4619'. Top perforations from 4558' to
4610'.
Squeezed bottom of well with 25 Sx. cement and 1 sack hulls. Maximum pump-
in pressure 200#. Final shut-in pressure 100#. Let cement set, shot off
4 1/2" and pulled to 750'. Circulated heavy gel mud. Pulled 4 1/2" to 690' and
displaced 20 Sx. cement thru 4 1/2". Pulled 4 1/2" to 450' and displaced 20 Sx.
cement thru 4 1/2". Pulled 4 1/2", set bridge @ 30' and 5 Sx. cement to bottom of
cellar. (Recovered 3400' 4 1/2" casing).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Nichols
Well Plugging Supervisor

DATE 5/11/67

INV. NO. 5196-W