

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
MAY 26 1969
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Morrison Producing Company,

Complete Address 400 North Main, Eldorado, Kansas.

Lease Name Deyer (BOYER) Well No. 1

Location CSW-NE Sec. 17 Twp. 20 Rge. (E) (W) 34

County Scott Total Depth 5017'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Leben Drilling Incorporated,

Address Box #486, Great Bend, Kansas. License No.

Operation Completed: Hour 2:00 PM Day 19 Month 5 Year 1969

The above well was plugged as follows:

349'--' 5/8" Surface casing, cement circulated with 325 Sx.
Top of Dakota section @ 650'.

Circulated hole with heavy mud. Pulled DP to 850' and displaced 100 Sx. cement thru
DP from 850' to 525'. Pulled DP to 370' and displaced 20 Sx. cement thru DP from
370' to 310'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. DeShole
Well Plugging Supervisor

DATE 5/27/69

INV. NO. 9844-w