

15-171-20002-0000

Form CP-3  
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 31 1967  
7-31-67  
CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Leben Drilling, Incorporated,

Complete Address: Box #486, Great Bend, Kansas.

Lease Name Easton Well No. 1

Location CSW-NE Sec. 20 Twp. 20 Rge. (E) (W) 34

County Scott Total Depth 5150

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A  X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Above

Address: \_\_\_\_\_ License No. \_\_\_\_\_

Operation Completed: Hour 4:00AM Day 26 Month 7 Year 1967

The Above well was plugged as follows:

445'--8 5/8" Casing cement circulated with 350 Sx.  
Dakota section from 1800' to 1965'.

Circulated hole with heavy mud, set plug thru DP from 2000' to 1700' with  
100 Sx. cement. Pulled DP to 430' and set plug thru DP from 430' to 370'  
with 20 Sx. cement. Pulled DP, filled hole with heavy mud to 40', set  
bridge with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 7/31/67  
INV. NO. 6047-W

Signed: N. L. Nichols  
Well Plugging Supervisor