

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 26 1965
5-26-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Glen Elden Oil Company,
Complete Address: Box #464, Eldorado, Kansas.
Lease Name Seeber Well No. 1
Location CSE-1/4 Sec. 31 Twp. 20 Rge. (E) (W) 32
County Scott Total Depth 2700
Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Bill Hay Drilling Company, Incorporated,
Address: 2007 Polk, Great Bend, Kansas. License No. 118
Operation Completed: Hour 5:00PM Day 22 Month 5 Year 1965

The Above well was plugged as follows:
325' --7" OD Surface pipe, cement circulated with 150 Sx.
2700' 4 1/2" Production casing cemented with 150 Sx. 6 1/4" hole below surface.
Bottom of well plugged back above all perforations.
Shot 4 1/2" casing @ 700', set bridge and displaced 25 Sx. cement thru 4 1/2".
Pulled 4 1/2" to 400' and displaced 25 Sx. cement thru 4 1/2". Pulled 4 1/2" to
300' and washed out excess cement. Left hole open from 300' to surface
at request of land owner to be used as irrigation well. (Authorization
attached)

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 5/26/65
INV. NO. 1220-W

Signed: *[Handwritten Signature]*
Well Plugging Supervisor