

DISTRICT CONSERVATION AGENT'S REPORT

TR

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 134-8

LOCATION NE-NE-SW

SEC. 1 TWP. 20 RGE. 34W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease J. Tava

Operator The Texas Co Address #614 - Bitting Bldg Wichita - Kans.

Field _____ County Scott

Total Depth 5185 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 3/4 - 340 ft. Circulated with cement.
7" casing set at 4600 ft. Lane Wells Plug at 4300 ft.
Mud to 4100 ft - Plug & 6 sacks of cement at 4100 ft -
Ripped off & pulled the 7" casing. Filled with mud to
340 ft - Set Rock Bridge & 20 sacks of cement at 340 ft -
Mud to 30 ft - Bridge & 10 sacks of cement at the surface.
R. S. Pipe Pulling Co - Plugging Contractors

E. H. Stouffer
District Conservation Agent

Date 1-29-50 1950

PLUGGING
FILE SEC 1 TWP 20 RGE 34W
BOOK PAGE 134 LINE 8

FEB 2-1-50
STATE CORPORATION COMMISSION
KANSAS