

15-171-20012-0000

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JAN 13 1969
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Glen Soderstrom,

Complete Address: 707 Barfield Building, Amarillo, Texas. 79601

Lease Name Skibbe Well No. 1

Location GSW-NE Sec. 31 Twp. 20 Rge. (E) (W) 31

County Scott Total Depth 4700'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Gabbert-Jones, Incorporated,

Address: 830 Sutton Place, Wichita, Kansas. License No.

Operation Completed: Hour 6:00 PM Day 8 Month 1 Year 1969

The Above well was plugged as follows:

289'--8 5/8" Surface casing, cement circulated with 250 Sx.
Top of Dakota section @ 1250'.

Circulated hole with heavy mud. Pulled DP to 1160' and displaced 100 Sx. cement thru
DP from 1160' to 835'. Pulled DP to 310' and displaced 20 Sx. cement thru DP from
310' to 250'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. D. Nichols
Well Plugging Supervisor

INVOICED

DATE 1/14/69
INV. NO. 9186-W