

15-077-30166-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
OCT 14 1966
10-14-66
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Mack Oil Company

Complete Address: 812 Union Center Bldg., Wichita, Kansas

Lease Name Hoath Well No. # 1

Location C SW SW Sec. 6 Twp. 33 Rge. 9 (E) W

County Harper Total Depth 4781'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Mack Oil Company

Address: 812 Union Center Bldg., Wichita, Kansas License No.

Operation Completed: Hour 11:30AM Day 9th Month Oct. Year 1966

The Above well was plugged as follows:

262' of 8 5/8" surface pipe, cement circulated with 200 sacks. Hole
was filled with drilling mud to 240', 1st cementing plug, bridged with
2 sacks of Gel-Mud and 1/2 sack of hulls on fluid at 240', and cemented
with 30 sacks, through the drill pipe. Hole was filled with drilling
mud to 60', 2nd cementing plug, bridged with 1 sack of Gel-Mud and 1/2
sack of hulls on fluid at 60', and cemented with 25 sacks. Rat and
mouse holes bridged and cemented with 5 sacks.

This cementing was done by Halliburton Cementing Company.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 10/14/66
INV. NO. 4094-U