

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-20922-00-00
Spot: NWNESW Sec/Twnshp/Rge: 16-26S-11W
2970 feet from N Section Line, 1650 feet from W Section Line
Lease Name: BURKNER Well #: 1
County: PRATT Total Vertical Depth: 4270 feet

Operator License No.: 32457
Op Name: ABERCROMBIE ENERGY, LLC
Address: 10209 W. CENTRAL, STE 2
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	10.75	255		WITH 325 SX CMT
PROD	5.5	4126	1660	WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/17/2011 1:00 PM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: JASON SCHULER Company: ABERCROMBIE ENERGY Phone: (620) 793-8186

Proposed Plugging Method: PUMP 200# HULLS & 30 SX CMT AT 3500'. PLUG AT 1680' WITH 15 SX GEL & 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 270' WITH 60 SX CMT. PLUG AT 60' WITH 15 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: NONE
Date/Time Plugging Completed: 08/17/2011 2:45 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

PUMPED 200# HULLS & 30 SX CMT AT 3500'. 1ST PLUG AT 1650' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 600' WITH 60 SX CMT. 3RD PLUG AT 270' WITH 60 SX CMT. 4TH PLUG AT 60' WITH 30 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
3619	3906		LANSING-KANSAS

RECEIVED
AUG 23 2011
KCC WICHITA

Remarks: **COMPLIANCE ISSUE: DENIED TA 10 YR RULE** USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED

AUG 19 2011

KCC DODGE CITY

Form CP 2/3