

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-001-30128-00-00
Spot: SENESENW Sec/Twnshp/Rge: 29-23S-20E
3574 feet from S Section Line, 2863 feet from E Section Line
Lease Name: FLEWHARDY Well #: 11
County: ALLEN Total Vertical Depth: 1100 feet

Operator License No.: 6168
Op Name: SCHEUNEMAN, LESTER
Address: 27800 PLEASANT VALLEY RD
WELLSVILLE, KS 66092

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	21		
PROD	2.875	1097		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/13/2011 12:00 AM

Plug Co. License No.: 7167 Plug Co. Name: LEACH, BRADLEY S. DBA LEACH WELL PULLING

Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: 10 SACKS AT TD. 10 SACKS AT 500'. 250' TO SURFACE.

Plugging Proposal Received By: _____

WitnessType: NONE

Date/Time Plugging Completed 04/13/2011 8:00 PM

KCC Agent: RYAN DULING

Actual Plugging Report:

Perfs:

Ran 1" pipe inside 2.875" casing to 1050'. Mixed and pumped gel. Pumped 10 sacks of cement through the 1" pipe at TD. Pulled 550' of 1" pipe. Pumped 10 sacks of cement through the 1" pipe at 500'. Pulled 250' of 1" pipe. Pumped cement from 250' to surface. Pulled the rest of the 1" pipe. Filled displacement. A total of 45 sacks of portland cement was reported used to plug this well.

RECEIVED

AUG 25 2011

KCC WICHITA

RECEIVED

AUG 23 2011

RMB

KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed _____

(TECHNICIAN)