

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-22582-00-00
Spot: SESWSWNW Sec/Twnshp/Rge: 22-22S-19E
2896 feet from S Section Line, 4698 feet from E Section Line
Lease Name: WEST COOPER Well #: 18
County: ANDERSON Total Vertical Depth: 880 feet

Operator License No.: 33097
Op Name: SOUTHERN STAR CENTRAL GAS PIPE
Address: 4700 HWY 56
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	7	20		
PROD	2.875	876		97 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/20/2011 12:00 AM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: STERLING BARKER Company: _____ Phone: (785) 448-4816

Proposed Plugging Method: RUN WORKSTRING TO BOTTOM, CEMENT TO SURFACE. TIE TO 2.875" SQUEEZE CEMENT UNTIL DESIRED AMOUNT OF CEMENT AND PRESSURE IS ACHIEVED. DIG OUT PIPE 3 FOOT BELOW SURFACE CUT, CAP AND BACKFILL.

Plugging Proposal Received By: LEVI SHORT WitnessType: NONE
Date/Time Plugging Completed: 04/20/2011 12:00 PM KCC Agent: LEVI SHORT

Actual Plugging Report:

RUN 1-INCH TUBING TO 876 FEET AND FILL TO SURFACE WITH CLASS A PORTLAND CEMENT THEN PRESSURE TO 500 POUNDS TO SHUT IN. A TOTAL OF 63 SACKS OF PORTLAND CEMENT WERE USED TO PLUG THE WELL.

Perfs:

Top	Bot	Thru	Comments
848	859		

RECEIVED
AUG 25 2011
KCC WICHITA

RECEIVED
AUG 15 2011 LS
KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed Li Short
(TECHNICIAN)