

TO: STATE CORPORATION COMMISSIO  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 6720

API Well Number: 15-001-22237-00-00  
Spot: SESWSW Sec/Twnshp/Rge: 21-26S-21E  
40 feet from S Section Line, 3530 feet from E Section Line  
Lease Name: NELSON Well #: H-30  
County: ALLEN Total Vertical Depth: 760 feet

Operator License No.: 33543  
Op Name: MORRISON, MARK L.  
Address: 1651 50TH RD  
YATES CENTER, KS 66783

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	7	48		32 SX
PROD	2.875	749		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/01/2011 12:00 AM  
Plug Co. License No.: 31519 Plug Co. Name: JACKSON, LELAND DBA LONE JACK OIL CO.  
Proposal Rcvd. from: MARK MORRISON Company: \_\_\_\_\_ Phone: (620) 496-7674

Proposed Plugging Method: RUN 1" POPE TO BOTTOM; CEMENT FROM BOTTOM TO TOP

Plugging Proposal Received By: \_\_\_\_\_ WitnessType: PARTIAL  
Date/Time Plugging Completed 04/01/2011 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe inside 2.875" casing to 700'. Mixed and pumped gel. Pumped 12 sacks of cement through 1" pipe. Pulled 300' of 1" pipe. Pumped 13 sacks of cement through 1" pipe to surface. Pulled rest of 1" pipe. Filled displacement. A total of 25 sacks of portland cement was reported used to plug this well.

Perfs:

RECEIVED  
AUG 23 2011 RMD  
KCC Chanute Dist. #3

RECEIVED  
AUG 25 2011  
KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed \_\_\_\_\_

(TECHNICIAN)