

TO:  
STATE CORPORATION COMMISSIO  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 6720

API Well Number: 15-001-30194-00-00  
Spot: NWNWNENE Sec/Twnshp/Rge: 3-24S-21E  
4964 feet from S Section Line, 1226 feet from E Section Line  
Lease Name: NORMAN UNIT Well #: 34  
County: ALLEN Total Vertical Depth: 750 feet

Operator License No.: 3728  
Op Name: KENT, ROGER DBA R J ENTERPRISES  
Address: 22082 NE NEOSHO RD  
GARNETT, KS 66032

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	7	20		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/14/2011 12:00 AM  
Plug Co. License No.: 3728 Plug Co. Name: KENT, ROGER DBA R J ENTERPRISES  
Proposal Rcvd. from: \_\_\_\_\_ Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: 50' PLUG AT TD. 50' PLUG AT 400'. CEMENT FROM 200' TO SURFACE.

Plugging Proposal Received By: \_\_\_\_\_ WitnessType: NONE  
Date/Time Plugging Completed 06/14/2011 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report: \_\_\_\_\_ Perfs: \_\_\_\_\_

Ran 1" pipe to 750'. Mixed and pumped gel. Pumped 12 sacks of cement through the 1" pipe at TD. Pulled 350' of 1" pipe. Pumped 12 sacks of cement through 1" pipe at 400'. Pulled 200' of 1" pipe. Pumped cement through 1" pipe from 200' to surface. Pulled the rest of the 1" pipe. Filled displacement. A total of 48 sacks of portland cement was reported used to plug this well.

RECEIVED  
AUG 23 2011 RMD  
KCC Chanute Dist. #3

RECEIVED  
AUG 25 2011  
KCC WICHITA

Remarks:  
Plugged through: TBG

District: 03 Signed [Signature]  
(TECHNICIAN)