

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-125-26602-00-01

Spot: SESWSENE

Sec/Twnshp/Rge: 1-33S-14E

2810 feet from S Section Line, 825 feet from E Section Line

Lease Name: DARBY

Well #: 18

County: MONTGOMERY

Total Vertical Depth: 1220 feet

Operator License No.: 5150

Op Name: COLT ENERGY INC

Address: PO BOX 388

IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
--------	------	------------	-------------	---------

SURF	6.625	20		8 SX
------	-------	----	--	------

PROD	2.875	1217		115 SX
------	-------	------	--	--------

Well Type: EOR

UIC Docket No: E23534.21

Date/Time to Plug: 07/18/2011 12:00 AM

Plug Co. License No.: 5491

Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP

Proposal Rcvd. from: REX ASHLOCK

Company:

Phone: (620) 365-3111

Proposed Plugging Method: RIH W/1" TBG TO BTM, PUMP 100' CMT PLUG @ BTM, THEN GEL SPACER, 50' CMT PLUG @500', GEL SPACER THEN CMT PLUG FROM 300' TO SURFACE, POOH REMAINDER OF TBG, "TOP OFF" CSG W/CMT, PRESSURE UP AND "CMT SQUEEZE", SHUT WELL IN. RETURN LATER AND CUT CSG OFF BELOW FLOW DEPTH.

Plugging Proposal Received By: DUANE SIMS

WitnessType: NONE

Date/Time Plugging Completed 07/18/2011 8:00 PM

KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1217' and pumped cement. Pulled 1" up 500' and circulated cement to surface. Pulled 1" and topped well off. Hooked onto well and pressured up to 450 psi. A total of 52 sacks of cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
1162	1171		

RECEIVED
AUG 25 2011
KCC WICHITA

RECEIVED

AUG 18 2011 DAS
KCC Chanute Dist. #3

Remarks: WELL PLUGGED BECAUSE IT WOULD NOT PASS MIT

Plugged through:

District: 03

Signed



(TECHNICIAN)

cc to UIC 8/26/11