

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-20089-00-00
Spot: SESWSW Sec/Twnshp/Rge: 33-15S-11W
330 feet from S Section Line, 4290 feet from E Section Line
Lease Name: DAVIDSON Well #: 9
County: RUSSELL Total Vertical Depth: 3288 feet

Operator License No.: 6883
Op Name: ROBINOWITZ OIL COMPANY, A GENE
Address: 4200 E SKELLY DR STE 620
TULSA, OK 74135

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	485	0	250 SX
PROD	5.5	3280	0	75 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/18/2011 8:30 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: DON DEGENHARDT Company: ROBINOWITZ OIL COMPANY Phone: (620) 587-3936

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 600# hulls - 13 sxs gel.
Perf: 1400' - 700' - 400'.

Plugging Proposal Received By: BRUCE BASYE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/18/2011 12:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 3100' - pumped 11 sxs gel - followed with 50 sxs cement with 100# hulls.
Pulled tubing to 1400' - pumped 70 sxs cement with 200# hulls.
Pulled tubing to 700' - pumped 115 sxs cement - circulated out the backside.
Closed valve and pumped 45 sxs cement - cement circulated out the Braden head.
POOH. Topped off casing with 5 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3280	3288		ARBUCKLE

Remarks: COPELAND CEMENTING AND ACID-TICKET #C37136.

Plugged through: TBG

RECEIVED
AUG 26 2011

KCC WICHITA

District: 04

Signed

Ray A. J. Kinkel

(TECHNICIAN)

CM

Form CP-2/3

AUG 18 2011