

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-23909-00-01  
Spot: SESWNENE Sec/Twnshp/Rge: 12-8S-18W  
1140 feet from N Section Line, 950 feet from E Section Line  
Lease Name: CARROL CONYAC Well #: 5  
County: ROOKS Total Vertical Depth: 3412 feet

Operator License No.: 34310  
Op Name: NEW AGE OIL LLC  
Address: 308 W. 38TH ST.  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	219	0	w/unknown sxs cmt
PROD	5.5	3392	680	w/unknown sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/17/2011 8:00 AM  
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING  
Proposal Rcvd. from: TRAVIS ROZEAN Company: NEW AGE OIL LLC Phone: (785) 623-0473

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls.  
Got out of the hole at 700'.  
Drilled to 3392'. Channeled to old hole - during completion - lost hole.  
PC at 1232'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/17/2011 3:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Sanded back to 3200'. Dumped two sxs cement at 3190'.  
Shot casing off at 1978' - laid one joint down.  
Quality Oil Well Cementing pumped 100 sxs 60/40 pozmix - 4% gel with 200# hulls.  
Unable to pull. Shot at 1612' and 1228' - no change.  
Pumped 80 sxs cement - displaced to 700'.  
Circulating Dakota sand up with drilling mud.  
Shot pipe free at 680' - pumped 140 sxs cement with 300# hulls - circulated with cement.  
Pulled casing out. Topped 8 5/8" with 30 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3372	3384		
3268	3271		

Remarks: QUALITY OIL WELL CEMENTING.  
Plugged through: CSG

RECEIVED  
AUG 26 2011  
KCC WICHITA

District: 04

Signed Richard Williams  
(TECHNICIAN)

CM

AUG 19 2011