

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21411-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 12-10S-18W
2310 feet from N Section Line, 2310 feet from E Section Line
Lease Name: HARRISON C Well #: 1
County: ROOKS Total Vertical Depth: 3854 feet

Operator License No.: 8914
Op Name: H & C OIL OPERATING INC.
Address: PO BOX 86
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	244	0	160 SX
PROD	4.5	3767	0	200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/18/2011 8:30 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: CHARLES R. RAMSAY Company: H & C OPERATING INC. Phone: (785) 434-2079

Proposed Plugging Method: Ordered out 350 sxs 60/40 pozmix - 4% gel - 500# hulls.
Casing leaks from 600' - 1900'.
Ran packer - got stuck at 3430' - could not move - decided to P/A.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/18/2011 1:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Tubing and packer stuck at 3430'.
Perf Tech backed tubing off at packer - screwed back into packer.
Quality Oil Well Cementing pumped 50 sxs 60/40 pozmix - 4% gel with 200# hulls.
Max. P.S.I. 1000#. S.I.P. 600#.
Unscrewed tubing from packer.
Pulled tubing to 3200' - pumped 50 sxs cement with 100# hulls.
Pulled to 2600' - pumped 75 sxs cement with 100# hulls.
Pulled tubing to 1450' - pumped 50 sxs cement with 100# hulls - cement circulated.
PTOH. Topped 4 1/2" casing with 15 sxs cement.
Hooked up to backside - pumped 10 sxs cement.
Max. P.S.I. 300#. S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
3591	3600		
3566	3572		
3508	3512		LANSING-KC

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: TBG

RECEIVED
AUG 26 2011
KCC WICHITA

District: 04

Signed Richard Williams
(TECHNICIAN)

CM

Form CP-2/3

AUG 19 2011