

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-16560-00-00  
Spot: NWNE Sec/Twnshp/Rge: 16-20S-15W  
660 feet from N Section Line, 3300 feet from W Section Line  
Lease Name: ADOLPH (STORAGE) Well #: 5  
County: BARTON Total Vertical Depth: 3815 feet

Operator License No.: 5399  
Op Name: AMERICAN ENERGIES CORPORATION  
Address: 155 N MARKET STE 710  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1035	0	w/unknown sxs cmt
PROD	5.5	3814	1750	w/unknown sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/09/2011 2:00 PM  
Plug Co. License No.: 31528 Plug Co. Name: MIKE KELSO OIL, INC.  
Proposal Rcvd. from: BARRY CONSIDINE Company: AMERICAN WNERGIES CORPORA Phone: (620) 755-2744

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/09/2011 5:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Sanded off perfs and topped with 5 sxs cement.  
Cut casing at 1750'.  
Pulled casing to 1650' - pumped 150 sxs cement with 200# hulls.  
Pulled casing to 1080' - pumped 50 sxs cement with 100# hulls.  
Pulled casing to 650' - pumped 125 sxs cement - circulated cement to surface.  
Pulled casing - hole stayed full.

Remarks: COPELAND ACID AND CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

CM

Form CP-2/3

AUG 10 2011

RECEIVED  
AUG 26 2011  
KCC WICHITA