

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-03415-00-00  
Spot: NWSWNW Sec/Twnshp/Rge: 24-11S-17W  
1650 feet from N Section Line, 330 feet from W Section Line  
Lease Name: COLAHAN A Well #: 4  
County: ELLIS Total Vertical Depth: 3420 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 1700 WATERFRONT PKWY BLDG 500  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1113	0	315 SX
PROD	5.5	3416	0	100 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/24/2011 8:00 AM  
Plug Co. License No.: 32452 Plug Co. Name: SMOKY HILLS WELL SERVICE  
Proposal Rcvd. from: JOEL STULL Company: VESS OIL CORPORATION Phone: (785) 483-9169

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 500# hulls.  
Prior squeezes: 180' w/210 sxs cwc; 1426' -1428' w/200 sxs; 1510' - 1540' w/200 sxs.  
Tubing anchor 1891'. Bad spot 1699'. Ran impression block to 1899'.  
Hole filled up to 2834'.  
Casing leak 1690' - 1698'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/24/2011 10:15 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Perf Tech perfered two shot hole at 1050'.  
Smoky Hill RIH with tubing to 1866'.  
Allied rigged to tubing and pumped 75 sxs 60/40 pozmix - 4% gel.  
Pulled tubing to 900'. Allied rigged to tubing and pumped 75 sxs neat - followed with 45 sxs cement with 250# hulls mixed in to circulate cement to surface.  
Pulled tubing - rigged to 5 1/2" casing with a swedge and pumped 55 sxs cement.  
Max. P.S.I. 150#. S.I.P. 100#.  
8 5/8" full from previous squeezes.

Perfs:


Top	Bot	Thru	Comments
3415	3420	OH	Arbuckle

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

  
(TECHNICIAN)

CM

RECEIVED  
AUG 29 2011  
KCC WICHITA

Form CP-2/3

AUG 24 2011