

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-22465-00-00  
Spot: NENWSW Sec/Twnshp/Rge: 33-15S-11W  
2310 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: DAVIDSON Well #: 10  
County: RUSSELL Total Vertical Depth: 3288 feet

Operator License No.: 6883  
Op Name: ROBINOWITZ OIL COMPANY, A GENE  
Address: 4200 E SKELLY DR STE 620  
TULSA, OK 74135

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3190		
CIBP		3306		
SURF	8.629	387	0	300 SX
PROD	5.5	3272	1794	150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/22/2011 8:30 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: DON DEGENHARDT Company: ROBINOWITZ OIL COMPANY Phone: (620) 587-3936

Proposed Plugging Method: Ordered 360 sxs 60/40 pozmix - 4% gel - 400# hulls.  
Cut casing at 1794' - leaving 1478' of 5 1/2" casing in the well.

Plugging Proposal Received By: BRUCE BASYE Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/22/2011 12:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

08/19/2011 - Sanded off bottom to 2925' and bailed 5 sxs cement on top.  
08/22/2011 - Cut casing at 1794'.  
Pulled casing to 1360' - pumped 100 sxs cement with 400# hulls.  
Pulled casing to 731' - pumped 25 sxs cement.  
Pulled casing to 428' - pumped 100 sxs cement - cement circulated.  
POOH. Pumped 5 sxs to top off surface pipe.

Perfs:

Top	Bot	Thru	Comments
3348	3350		ARBUCKLE
3313	3314		ARBUCKLE
3298	3300		ARBUCKLE
3288	3290		ARBUCKLE
3150	3154		LKC
2988	3002		LKC

RECEIVED  
AUG 29 2011  
KCC WICHITA

Remarks: COPELAND ACID AND CEMENTING COMPANY-TICKET #C37139.

Plugged through: CSG

District: 04

Signed

Ray A. Dinkel

(TECHNICIAN)

CM

Form CP-2/3

AUG 24 2011