

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-21275-00-00
Spot: SESE Sec/Twnshp/Rge: 9-32S-18W
682 feet from S Section Line, 639 feet from E Section Line
Lease Name: WILLBANKS Well #: 1-9
County: COMANCHE Total Vertical Depth: 5328 feet

Operator License No.: 5047
Op Name: RUPE OIL COMPANY, INC.
Address: 111 WHITTIER # 1000 PO BOX 783010
WICHITA, KS 67207

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	690		WITH 240 SX CMT
COND	20	60		
PROD	5.5	5327	3010	WITH 180 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 08/24/2011 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP DOWN 5 1/2" CASING WITH 200# HULLS & 25 SX CMT. PLUG AT 850' WITH 10 SX GEL & 75 SX CMT. PLUG AT 280' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: PARTIAL
Date/Time Plugging Completed: 08/24/2011 4:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PUMPED DOWN 5 1/2" CASING WITH 200# HULLS & 25 SX CMT. TAG TOC @ 4875'.
1ST PLUG AT 1060' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 700' WITH 50 SX
CMT. 3RD PLUG AT 300' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5130	5133		


RECEIVED
AUG 29 2011
KCC WICHITA

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed


(TECHNICIAN)

RECEIVED

AUG 25 2011

KCC DODGE CITY

Form P-2-09